



Main: (616) 243-6374
 Customer Support: (616) 243-5434

**SERVICE
 REPAIR/REPLACEMENT
 PROPOSAL**

DATE: 01/07/2026

Pleune Service Company excludes any work connected or associated with hazardous materials including but not limited to any pollutant, asbestos-containing materials, mercury, lead or mold. Customer shall be solely responsible for the presence of any hazardous materials at the worksite and shall indemnify and defend PSC and its subcontractors from any claims, damages, losses and expenses, including attorney fees, arising out of the presence of any hazardous materials on Customer's premises, except that Customer is not responsible to the extent that any claim, damage, loss or expense is caused directly by the negligent acts of PSC.

QUOTE ID:	20256	CONTACT:	JUSTIN STADT
SERVICE LOCATION:	GEORGETOWN CHARTER TWP OFFICES		Ph:(616) 457-2340
			Fax:(616) 457-3670
STREET:	1515 BALDWIN ST		jstadt@georgetown-mi.gov
CITY:	JENISON, MI 49429	DATE SUBMITTED:	01/07/2026
		PREPARED BY:	DRAYTON, HARRISON

DESCRIPTION:

2026 Updated: Condenser and Coil Replacement for Air Handlers #3 and #4

SCOPE OF WORK:

Pleune Service Company is pleased to provide this quote to replace the Air Conditioning side of Air Handlers #3 and #4. This includes the indoor Evaporator Coil and outdoor Condensing Unit. This quote includes the following materials and scope of work.

- We will remove and dispose of the 10ton and 15ton Condensers and Coils.
- We will install new Evaporator Coils in each of the Air Handlers listed and we will replace the existing Expansion Valves and Solenoids.
- We will install new Condensing units that will be connected to each of the new Evaporators and we will replace the Liquid Line Dryers.
- Copper piping between both systems will be cleaned and pressure tested prior to re-connection.
- We will replace any tattered piping insulation.
- We will reconnect the system to the existing condensate piping, electrical, and controls.
- We will perform the initial start-up of the equipment and check it for proper operation.
- This quote is figured with all work being done during normal business hours.
- Please note that there is a 3-4 business day lead time on the equipment. The equipment quoted is based on stock availability, today.

Exclusions: Prevailing wage and state granted work requirements. This quote does not include any engineering or load calculations, the new unit sizing is based off of the existing unit information. Also, this quote does not include any cost for prints or plan review, if these items are required by the inspector it would be at an added cost to the project. Unless noted in the quote all existing items will be reused. This quote does not include any cost for repairs or modifications due to existing code violations if any are found, this includes any safety rails and access ladders. Credit / Debit payments not accepted.

Thank you for the opportunity to bid this project. If you have any questions please call me.

Harrison Drayton | Service Replacement Sales
 C. (616) 430-3082 | hdrayton@pleuneservice.com

ITEM	TOTAL
Total	\$58,646.30

SIGNATURE

PRINT NAME

DATE

This proposal is a binding contract.

The above specifications, terms and conditions are satisfactory and (I) (we) hereby authorize the performance of this work.

Please sign and return this contract as authorization to commence work. Please email to dispatch@pleuneservice.com.

Prices are subject to change after 7 days from the date the original proposal was sent, unless otherwise noted in the body of this quote.